Farrar Green Home

www.FarrarGreenHome.org

WE 2.1 Irrigation System

a) Irrigation system designed by EPS Water Sense certified professional
b) Irrigation system does not have head to head coverage
c) Central shut off valve from well
d) Separate water supply from well
e) Drip irrigation for 77% of planting beds
f) 31 separate zones for each type of bedding area based on watering needs
g) Smart home controller that activates valves for each zone at best time of day
h) Pressure regulating devices on drip line
i) Average DU not calculated
j) No check valves in heads
k) Rain delay controller based on internet access by Smart home controller